



SWALE & TREE WORKS QUOTATION/CONTRACT

DATE: [REDACTED] QUOTE No.2011-0054

CLIENT'S TRADE NAME: [REDACTED]

CLIENT'S FULL or LEGAL NAME: [REDACTED]

Phone: _____ Fax: _____

Mobile: _____ Email: _____

Billing Address: [REDACTED] Physical Address: [REDACTED]

State: [REDACTED] Post-code: [REDACTED] State: [REDACTED] Post-code: [REDACTED]

DETAILS OF WORKS TO BE SUPPLIED: See next page for inclusions & exclusions.	QUANTITY	PRICE \$ (Excl. GST)
1) Hire of Yeomans Plow - To complete area around Swale 1. _____	2 Days _____	\$1800.40 _____
2) Travel from Queanbeyan to Nambrok return - (1068 km @ \$1.02 per km) _____	1068 km _____	\$1038.10 _____
3) Accommodation for 7 nights at Sale Motor Village _____	7 nights _____	\$1680.00 _____
4) Swale Trees 4 + Dam - 285 Trees + 30 Bamboo on the Dam wall trees 24 on swale x-over_(Guards on Separate quote) - 339 _____	_____	\$14'023.08 _____
5) Swale Construction 1 - 145m long - 725 m2 _____	145m _____	\$3030.48 _____
6) Swale construction 2 - 762m long - 3810 m2 _____	762m _____	\$7239.77 _____
7) Swale construction 3 - 581m long - 2905 m2 _____	581m _____	\$5976.26 _____
8) Swale construction 4 - 160m long 800 m2 _____	160m _____	\$1936.44 _____
9) Swale Construction 5 - 70m long - 350 m2 _____	70m _____	\$1280.28 _____
10) Swale Construction 6 - 130m long - 650 m2 _____	130m _____	\$1744.92 _____
11) Swale Construction 7 - 130m long - 650 m2 _____	130m _____	\$1744.92 _____
12) Swale Construction 8 - 110m long - 550 m2 _____	110m _____	\$1617.24 _____

Bank Account Details for Payment:
 Bendigo Bank: BSB [REDACTED] Acc [REDACTED]

TOTAL PRICE \$ (Excl. GST) \$43,111.89 _____
 GST \$4311.18 _____
 TOTAL PRICE \$ (Incl. GST) \$47,423.03 _____

DELIVERY DATE: 28/03/11 - PAYMENT TERMS ARE: 30% deposit on acceptance of quotation. Final 70% due on completion handover within 7days.

THIS QUOTATION REMAINS VALID FOR 30 DAYS FROM THE ABOVE DATE AFTER WHICH A REVISED QUOTE MAY BE NECESSARY. ANY VARIATION TO THE ABOVE QUANTITIES MAY RESULT IN A VARIATION TO THE QUOTED PRICE.

I accept this quotation and certify that the above information is true and correct. I have read and understand the TERMS AND CONDITIONS OF TRADE (overleaf or attached) of GLOBAL LAND REPAIR Pty. Ltd which form part of, and are intended to be read in conjunction with this Quotation Form and agree to be bound by these conditions. I authorise the use of my personal information as detailed in the Privacy Act clause therein. *I agree that if I am a director or a shareholder (owning at least 15% of the shares) of the Client I shall be personally liable for the performance of the Client's obligations under this contract.*

CONTRACTOR TO SIGN	CLIENT TO SIGN
SIGNED: [REDACTED] _____	SIGNED: _____
Name: [REDACTED] _____	Name: _____
Date: 26th of February 2011 _____	Date: _____ DOB: _____

Global Land Repair Pty. Ltd (incorporating "the plant pink system")
 P.O. Box 659, FYSHWICK, ACT NSW 2609, AUSTRALIA. Ph: [REDACTED]
 Web: [REDACTED] Email: [REDACTED]



Inclusions:

- Hire of Yeomans Keyline Plow to complete unfinished soil de-compaction from last visit. Also preparation of tree planting for Stage 3. Included is hire of the Plow.
- Travel to site: Queanbeyan NSW to Nambrok Vic return @ \$1.02 per km. Included is travel, Fuel and general car costs. (Increase of \$0.21 per km due to fuel price rise).
- Permaculturalist (Nicholas Huggins) – Certified PDC Teacher & Design Consultant. HORTICULTURALIST – DIPLOMA HORTICULTURE 2001, CERT 3 LANDSCAPE DESIGN 1999
- Accommodation for all Global Land Repair staff at Sale motor village for 7 nights.
- Swale Trees 4 – Tree Guards, Weed mat, Stake, Mycorrhiza fungi, planting gel, Tree Starter and tree tonic will be issued on a individual invoice for payment.
- Swale Trees 4 – Includes: Tube stock of 285 trees, Mulching of trees, Labour to plant trees.
- Swale Trees 4 – Bamboo will be used to stabilize the dam wall and provide shade to the dam inc will be labour and bamboo + delivery to site. (This bamboo is not invasive).
- Swale Crossover Pipe – Swales 1–3 will have swale crossover pipes to get cattle and equipment across the swale. 300mm pipe will be installed, 4 bamboo will be planted each side of the swale pipe to funnel cattle and to support the walls of the crossing.
- Swale Construction 1 to 4, are the 4 major water harvesting swales and include: Grader Hire and float, 5 tonne excavator inc float and driver, 300mm x 6m Plastic pipe for swales 1 to 3 inc delivery installation and labour, 7mm fill gravel for the crossover road, Cover crop seed inc application and labour, Straw bales inc delivery – labour and transport to site, and the use of a lazer level for the 7 days.
- Swale Construction 5 to 8, are the 4 minor water harvesting swales and these will form the animal fodder and forrage systems and the construction includes: Grader Hire and float, 5 tonne excavator inc float and driver Cover crop seed inc application and labour, Straw bales inc delivery – labour and transport to site, and the use of a lazer level for the 7 days.
- All labour costs for Global Land Repair staff and sub-contractors is included in price per item.
- Swale Construction 4 – The price for this swale will include improvements to the dam wall and increasing the holding capacity by 1/3 and will be incorporated into the swale which will feed the dam over time.
- Trees from Stage 1 – We will be repalcing any sick or dead trees on this visit at no extra charge.

Exclusions:

- Watering of the trees to be undertaken by the McGauran Family.
- Follow up watering not included in price. Maintenance not included.
- Swale Trees 4 – 160m Long, 285 Trees– Tree selection is still to be approved by clients. Global land Repair recommends trees sourced from Eucacia Native Nursery 56 Briagolong – Stockdale Road Briagolong 3860 Ph (03) 5145 5627
- Hire of Yeomans Keyline Plow: No Tractor is included in the cost of plow hire. Use of the farm Tractor would reduce and external hire cost or subcontractors.
- We will require the use of the Farm Tractor again and also the round bale side feeder. Labour to drive the machinery included.
- Tree Guards and associated planting materials have not been included in this quotation.

What is a Prime cost Item?

A Prime Cost (PC) item is an allowance in the contract for fixtures and items that the owner is to select after the contract has been signed. This may include types of specific trees..

What is a Provisional Sum Item?

A Provisional Sum (PS) item is generally included in the contract in circumstances where the contractor is unable to give a definite price for aspects of the work and where the owner is still to make some choices about the items and work to be done.

Global Land Repair Pty. Ltd (incorporating "the plant pink system")
P.O. Box 659, FYSHWICK, ACT NSW 2609, AUSTRALIA. Ph: [REDACTED]
Web: [REDACTED] Email: [REDACTED]